

TOWN OF HARWICH, MA

WIXON LANDING PIER IMPROVEMENTS

PRE-BID QUESTIONS

1. Please reference Specification 02 10 00 (Site Preparation) paragraph 1.05 and advise if the Pier and Parking Area is to remain open to the public during construction?

**The public landing, ramp and float will be closed to the public during construction.
The road leading to private home and business will need to remain open for access.**

2. Please reference Specification 02 10 00 (Site Preparation) paragraph 3.01C and confirm that Vibration Monitoring is to be performed 2-weeks prior to start of construction?

Vibration Monitoring is not required for this project.

3. Please reference Drawing C-02 showing locations of Timber Post & Rail. Please confirm that the Timber Post & Rail on both side of the Permeable Walkway Path is to be included in Bid Item #Alt 1-1 and not included in Bid Item #4?

Yes, the post and rail on both sides of the Permeable Walkway Path is included on Bid Item Add Alt #1. It is not included in Bid Item #4.

4. Please reference Drawing C-02 and confirm that the spacing of posts for the Timber Post & Rail is 3.5-ft on center?

The spacing of the posts for the Timber Post & Rail should be 6 ft on-center, not 3.5 ft.

5. Please reference Drawing C-03 Detail H showing Permeable Walkway Paver and confirm that no subgrade material is needed for the 3" thick Paver?

No subgrade material that hardens making the permeable walkway impervious should be used.